Sl. No.	Description of work	Mesurement				Qty	Unit	Rate	Amount
		No	L	B	D				
15	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20 mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.6 Page No. 13/ Item No. 4.11/ PWD SR 2015-16								
	Basic Rate	5739	344.34	6083.34					
	Sump	1	2.60	3.40	0.15	1.33			
	Lintel	1	24.00	0.20	0.15	0.72			
						2.05	**cum**	**6083.34**	**12,446**
16	Providing and installing of per painted Galvolume Iron Trapezoidal Profiled Sheet of approved mark 1060 mm width (1000mm Cover width)28-30mm crest height with crest distance of 200mm c/c with 2 ribs at the center for stifening the total coated thickness TCT of the sheet will be 0.47 mm +--0.02mm tolerance Zinc Alu alloy coating AZ 150 gsm as per ASTm 1397/A755-550 Page No.291/ Item No. 38.30/ PWD SR 2015-16								
	Basic Rate	770	46.2	816.2					
		1	10.00	6.00		60.00			
						60.00	**Sqm.**	**816.20**	**48,972**
17	KSRB 15.3.7 : Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 112/ Item No. 15.15 / PWD SR 2015-16								
	Basic Rate	231	13.86	244.86					
	Parapet Wall	1	4.80	1.45		6.96			
		1	5.20	0.20		1.04			
		1	5.20	0.40		2.08			
						10.08	**cum**	**244.86**	**2,468**
18	KSRB 14.13.2: Providing precast chequered mosaic tiles light shade using ordinary grey cement for steps and flooring, with precast 20mm thick, using marble chips of approved colour 7 to 10 nominal size laid in floors,steps and landings on a bed of 12mm thick cement mortar 1:6, mix, jointed with neat cement slurry mix with pigment to match the shade of tiles curing, rubbing, polishing , oxalic acid wash, wax polish, including cost of materials, labour, HOM machinery complete as per specifications. Specification No. KBS 14.13,14.14 Page No. 105/ Item No. 14.29 / PWD SR 2015-16								
	Basic Rate	1038	62.28	1100.28					
		1	7.80	3.80		29.64			
						29.64	**cum**	**1100.28**	**32,612**

Sl. No.	Description of work	Mesurement				Qty	Unit	Rate	Amou
		No	L	B	D				
19	KSRB 14.14.3: Providing white glazed tiles of size 15 cms x 15 cms 6mm thick for flooring, treads of steps and landing, laid on a bed of 12mm) thick, cement mortar 1:3 mix, flush pointing using white cement including cost of materials, labour, complete as per specifications. Specification No. KBS 14.15.1. Page No. 103/ Item No. 14.34 / PWD SR 2015-16								
	Basic Rate	**718**	**43.08**	**761.08**					
		2	1.00	8.60	2.00	34.40			
		1	1.00	4.60	1.50	6.90			
		1	1.00	8.50	1.20	10.20			
						51.50	**cum**	**761.08**	**39,195**
20	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including curing etc., Page No. 108/ Item No. 14.49 / PWD SR 2015-16								
	Basic Rate	**3452**	**207.12**	**3659.12**					
		1	1.00	2.15	1.00	2.15			
		1	1.00	5.20	1.00	5.20			
	Deduct Doors	-1	2.00	0.75	2.00	-3.00			
						4.35	**Sqm.**	**3659.12**	**15,917**
21	KSRB 11.9.1 : Providing and fixing white vitreous china clay, flat back or half stall urinal basin of size 580x380x350mm with 5 liters PVC automatic flushing cistern, C.I./M.S. brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps C.I. draft with outlet grating and other coupling in C.P. brass, painting of fitting and brackets cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. Page No. 77/ Item No. 12.5 PWD SR 2015-15								
	Basic Rate	**4981**	**298.86**	**5279.86**					
		2				2.00			
						2.00	**Each**	**5279.86**	**10,559**
22	KSRB 11.9.1 : Providing and fixing white vitreous china clay, flat back or half stall urinal basin of size 580x380x350mm with 5 liters PVC automatic flushing cistern, C.I./M.S. brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps C.I. draft with outlet grating and other coupling in C.P. brass, painting of fitting and brackets cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. Page No. 79/ Item No. 12.15 PWD SR 2015-15								
	Basic Rate	**4871**	**292.26**	**5163.26**					
		3				3.00			
						3.00	**cum**	**5163.26**	**15,489**

Sl. No.	Description of work	Mesurement				Qty	Unit	Rate	Amount
		No	L	B	D				
23	KSRB 11.11.1 : Providing and fixing white vitreous china clay, flat back wash basin of size 630x450mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets ,cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11, Page No. 80/ Item No. 12.23 PWD SR 2015-16								
	Basic Rate	3709	222.54	3931.54					
		2				2.00			
						2.00	**Each**	**3931.54**	**7,863**
24	KSRB 11.11.3 : Providing and fixing white vitreous china clay, flat back wash basin of size 550x400mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11, Page No. 81/ Item No. 12.25 PWD SR 2015-16								
	Basic Rate	3557	213.42	3770.42					
		2				2.00			
						2.00	**Each**	**3770.42**	**7,540**
25	KSRB 11.15.1: Providing and fixing 600x450mm bevel lead edge mirror of superior glass with 6mm hard board backing and fixed to wooden cleats with C.P crews, washers, including cost materials, labour complete as per specifications. Page No. 82/ Item No. 12.39 PWD SR 2015-16								
	Basic Rate	1242	74.52	1316.52					
		2				2.00			
						2.00	**Each**	**1316.52**	**2,633**
26	KSRB 11-18-17.1 Providing and fixing sand cast iron trap of 100mm dia, of self cleaning design with screwed down or hinged grating with or without vent arm including cutting and making good the walls and floors, cost of materials, labour, testing, complete as per specifications. Specification No. KBS 11-1.10 Page No. 86/ Item No. 12.89 PWD SR 2015-16								
	Basic Rate	826	49.56	875.56					
		5				5.00			
						5.00	**Each**	**875.56**	**4,377**
27	Providing vulcanizing or rubber float of approved 1st quality and make conforming to ISI Specifications and fixing for for low down cistern as directed. Rate includes cost of materials and conveyance to work spot. Page No. 87/ Item No. 12.106 PWD SR 2015-16								
	Basic Rate	180	10.8	190.8					
		3				3.00			
						3.00	**Each**	**190.80**	**572**

Sl. No.	Description of work	Mesurement				Qty	Unit	Rate	Amoun
		No	L	B	D				
28	Providing wash basin brackets of approved 1st quality and make conforming to ISI Specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot. Page No. 87/ Item No. 12.107PWD SR 2015-16								
	Basic Rate	228	13.68	241.68					
		2				2.00			
						2.00	**Pair**	**241.68**	**483**
29	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia Page No. 88/ Item No. 12.111 PWD SR 2015-16								
	Basic Rate	160	9.6	169.6					
		5				5.00			
						5.00	**Each**	**169.60**	**848**
30	Providing stoneware gully trap of approved quality and make fixing in CC 1:2:4 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead), for 10cms x 10 cms Page No. 88/ Item No. 12.112.1 PWD SR 2015-16								
	Basic Rate	185	11.1	196.1					
		5				5.00			
						5.00	**Each**	**196.10**	**980**
31	Providing and fixing CI Nahani Trap of approved make conforming to ISI specifications and construction of cistern in CC 1:2:4 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot) for 10 cms x 7.5cms (Page. 85 Item 12.113) Page 88 Item 12.113.1 PWD SR 2015-16								
	Basic Rate	250	15	265					
		2				2.00			
						2.00	**Each**	**265.00**	**530**
32	KSRB 13.3.3: Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 25mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments complete as per specifications. Specification No. KBS 13.2.14 /13.6 Page No. 90/ Item No. 13.12 / PWD SR 2015-16								
	Basic Rate	267	16.02	283.02					
		25				25.00			
						25.00	**Mts.**	**283.02**	**7,075**
33	KSRB 13.3.2: Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 20mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments complete as per specifications. Specification No. KBS 13.2.14 /13.6 Page No. 90/ Item No. 13.11 / PWD SR 2015-16								
	Basic Rate	185	11.1	196.1					
		25				25.00			